

# High-voltage test system HPG 50-H - 110-H

## Compact and powerful AC test systems



- Compact, maintenance free, cast-resin highvoltage transformers
- Separate control and HV units
- Continuously adjustable voltage
- A powerful system: continuous operation at 1.2 kVA; 60 min. short operation at up to 3 kVA
- DC testing via a rectifier

#### **DESCRIPTION**

The AC voltage test sets HPG 50, 80 and 110-H are suitable for 50 / 60 Hz AC testing of low capacity test objects. Optionally, these units can also be upgraded to function as DC test sets by mounting the rectifier attachment on top of the transformer.

#### Typical application areas:

- Testing switchgears
- Testing voltage and current transformers
- Testing MV plants/components
- DC cable testing

The two piece design allows the operator to use the unit at a safe distance. The control unit is used to operate the high voltage transformer. The unit consists of a variac, current/ voltage display instruments, a timer for the test duration and a safety circuit. The low voltage winding can be continuously excited from zero to the maximum value so that a certain output is available for a pre-determined period. The operating duration depends on the application, ranging from a few minutes to continuous operation.

#### All HPG test systems at a glance:

- HPG 50-H, testing up to 35 kVRMS / DC-testing up to 50 kV
- HPG 80-H, AC testing up to 58 kVRMS / DC-testing up to 80 kV
- HPG 110-H, AC testing up to 78 kVRMS / DC-testing up to 110 k

#### All HPG test systems at a glance:

- Continuous testing with AC voltages up to 1.5 kVA
- Separate control and HV-unit
- In-built over-current protection
- DC-testing via rectifier attachment

# High-voltage test system HPG 50-H - 110-H Compact and powerful AC test systems

#### **TECHNICAL DATA\***

	HPG 50-H	HPG 80-H	HPG 110-H
Power consumption P <sub>N</sub>	1.2 kVA	1.2 kVA	1.5 kVA
Power consumption			
short-time P <sub>k</sub> (1h)	3 kVA	2.5 kVA	3.5 kVA
Input voltage	230 V / 50 60 Hz	230 V / 50 60 Hz	230 V / 50 60 Hz
Output voltage	0 35 kV <sub>rms</sub> AC	0 58 kV <sub>rms</sub> AC	0 78 kV <sub>rms</sub> AC
	0 50 kV DC	0 80 kV DC	0 110 kV DC
Measuring range	0 40 kV AC	0 60 kV AC	0 80 kV AC
	0 60 kV DC	0 80 kV DC	0 110 kV AC
Precision	1.5 %	1.5 %	1.5 %
Ausgangsstrom	0 15mA	0 15mA	0 15mA
	50 mA (1 hour)	50 mA (1 hour)	50 mA (1 hour)
Measuring range	0 500 μA/ 0 50 mA	0 500 μA/ 0 50 mA	0 500 μA/ 0 50 mA
Control unit HSW 3-2			
Weight	26 kg / 57.3 lbs.	26 kg / 57.3 lbs.	26 kg / 57.3 lbs.
Dimensions (W x H x D)	520 x 255 x 320 mm	520 x 255 x 320 mm	520 x 255 x 320 mm
	20.5 in. x 10.0 in. x 12.9 in.	20.5 in. x 10.0 in. x 12.9 in.	20.5 in. x 10.0 in. x 12.9 in.
Transformer			
Weight	48 kg / 105.8 lbs.	76 kg ./. 167.6 lbs.	95 kg / 209.4 lbs.
Dimensions (W x H x D)	440 x 320 x 420 mm 17.3 in. x 12.6 in. x 16.5 in.	440 x 440 x 440 mm 17.3 in. x 17.3 in. x 17.3 in.	310 x 720 x 310 mm 12.2 in. x 28.3 in. x 12.2 in.

ORDERING INFORMATION		
Product	Order no	
<b>HPG 50-H</b> Control unit (HSW 3-2), HV-transformer 78 kV <sub>rms</sub> , set of cables, rectifier attachment, discharge and earthing rod 50 kV	81 3220	
<b>HPG 80-H</b> Control unit (HSW 3-2), HV-transformer 58 kV <sub>rms</sub> , set of cables, rectifier attachment, discharge and earthing rod 100 kV		
HPG 110-H Control unit (HSW 3-2), HV-transformer 78 kV <sub>rms</sub> , set of cables, rectifier attachment, discharge and earthing rod 150 kV		
Options:		
HV-connection cable 3 m (unshielded)		
HV-connection cable 5 m (unshielded)	200 4993	
HV-connection cable 10 m (unshielded)	200 5030	
HV-connection cable 5 m (shielded)	81 000 3736	
HV-connection cable 10 m (shielded)	82 002 3906	

<sup>\*</sup> We reserve the right to make technical changes.



Megger Germany GmbH Dr.-Herbert-lann-Str. 6 96148 Baunach Germany T +49 9544 68-0 E team.international@megger.com

### HPG50-110H\_DS\_EN\_V03

www.megger.com



